Improving and extending Rampur Channel, Nanjangud Taluk, Mysore District.

Statement showing the approximate quantities of work in each contract section.

	Per	No. 2 Contract Section. 0 to 1st Mile.	No. 3 Contract Section. 1st to 3rd Mile.	No. 4 Contract Section. 3rd to 5th Mile.	No. 5 Contract Section. 5th to 6th Mile.	No. 6 Contract Section. 6th to 7th Mile.	No. 7 Contract Section. 7th to 8½ Mile.	No. 8 Contract Section. 8½ to 9th Mile.	No. 9 Contract Section. 9 to 9½ Mile.	No. 10 Contract Section. 9½ to10th Mile.	No. 11 Contract Section. 10 to 12th Mile.	No. 12 Contract Section. 12th to 14th Mile	No. 13 Contract Section. 14 to 15th Mile.	No. 14 Contract Section. 15 to 17½ Mile.	No. 15 Contract Section. 17½ to 20¼ Mile.	No. 16 Contract Section. 20¼ to 22nd mile.	No. 17 Contract Section bridges. 0 to 22nd Mile.
Excavation	C. yd.	45,422	48,814	2,27,484	27,308	23,558	19,057	8,130	12,578	10,599	26,749	34,247	17,066	17,526	38,698	24,282	3,411
Stone in surki mortar	C. ft.	4,371	...	...	...	...	...	...	...	...	...	...	...	...	...	3,309	16,940
Cut stone in do	Do	1,301	...	...	...	...	...	...	...	...	...	...	...	...	...	294	...
Brick in do	Do	4,622	1,188	10,804	1,188	11·88	1,980	396	396	3·96	2,772	2,376	1,584	2,887	2,772	1,647	396
Do archwork do	Do	703	...	...	...	...	...	...	...	...	...	...	...	12	...	8,409	...
Pointing with surki mortar	Sqr.	14·30	...	...	...	...	...	...	...	...	...	...	...	0·45	...	5·98	42·24
Plastering with do	Do	34·96	5·92	13·56	3·84	3·84	6·40	1·28	1·28	1·28	8·96	7·68	5·12	9·65	8·96	225·59	11·02
Surki concrete	C. ft.	460	...	126	...	...	...	...	...	...	...	80	...	118	...	4,342	3,796
Slab stones	Do	687	68	22	9	9	153	3	3	3	61	18	12	45	21	6,534	1,524
Cordor work	R. ft.	250	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Earthwork	C. yd.	320	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Teak wood beams	C. ft.	66	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Rough stone revetment	C. yd.	101	...	574	...	...	...	...	...	...	...	623	...	540	...	23	...
Shutters for head and scouring sluices (5—7′ × 5′—10″)	Each.	7	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Repairs and improvements to waste weirs, &c., will be paid at tendered rates. Quantity of work as may be required	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Carriage of iron pipes and fixing	Each.	3	9	14	6	6	10	2	4	2	14	14	12	12	18	4	...
Brick in mortar	C. ft.	..	844	...	...	...	1,727	...	...	...	238	904	...	1,448	...	...	...
Stone in mortar	Do	...	227	...	...	...	...	...	...	...	150	...	...	...	...	...	...
Plastering with mortar	Sqr.	...	...	...	...	...	11·08	...	...	...	1·35	4·58	...	7·36	...	...	...
Shutters (5½′ × 7′)	Each.	...	...	...	...	...	1	...	...	...	...	...	...	...	...	...	...
Embankment including consolidation	C. ft.	...	...	...	...	...	...	...	...	...	...	4,098	2,116	17,363	...	...	...
Shutters with iron work complete (2½ × 1½)	Each.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Cut stone in mortar	C. ft.	...	...	...	...	...	...	...	...	...	...	...	...	15	...	...	...
Centerings	L. S.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...
Cornice work	R. ft.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1,669	...
Approaches	C. yd.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	about (2,000)	...
Benching rock	C. ft.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	about (3,000)	...
Pillars, beams and corbel stones	To	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	1,347
Metalling and gravelling	C. yd.	...	...	...	...	...	...	...	...	...	...	...	...	...	...	...	40

Note.—General repairs and improvements, rough stone work, old and new, to weirs, silt dams, aprons and revetments to be executed where required must be tendered for at per cubic yard.

Alternative rates for masonry works in ordinary mortar and in surki mortar to be tendered.

G. H. BAYLY,
Executive Engineer.